



GEOTECHNICAL & MATERIALS ENGINEERING, TESTING & INSPECTION P.O. BOX 15732 - TAMPA, FLORIDA 33614 - 813/872-7821 CA No.1450

PROJECT:

Product Check - P.O. No. 7001-95000

PROJECT NO:

TL-8047

53rd St. Yard

CLIENT:

Transcor Recycling LLC

DATE:

2/7/2017

LAB NO .:

21990

SAMPLE LOCATION:

Stockpiled at 53rd Street Yard

SAMPLE DESCRIPTION:

Crushed Concrete Fines

Sieve Number	Percent Passing
3/4"	100
3/811	93
No. 4	75
No. 10	64
No. 50	38
No. 100	19
No. 200	5.9

DATE SAMPLED:

1/26/17

DATE TESTED:

2/1/17

This report contains information that is intended solely for the use of the client and noted assigns.




GEOTECHNICAL & MATERIALS ENGINEERING, TESTING & INSPECTION


P.O. BOX 18732 • TAMPA, FLOREDA 33684 • 813/872-7821 CA No. 1460

Product Check - P.O. No. 7001-95000

53rd St. Yard

CLIENT: Transcor Recycling LLC





LIMEROCK BEARING RATIO TEST TEST METHOD: FDOT FM 5-515

PROJECT NO:

TL-8047

DATE:

February 7, 2017

LAB NO:

21990

LBR TEST NO:

163

COMPACTION TEST NO .:

186

MAXIMUM LBR VALUE (%):

103

MAXIMUM DRY DENSITY (PCF):

118.5

OPTIMUM MOISTURE (%):

11.6

DATE RECEIVED:

01/26/17

DATE TESTED:

02/03/17

LOCATION SAMPLED: Stockpiled at 53rd St. Yard

SOIL DESCRIPTION:

Crushed Concrete Fines

TYPE OF MATERIAL: Base

SOAKING TIME (HRS): 48±4 SOAKING SURCHARGE (LBS): 2.5 TESTING SURCHARGE (LBS): 0

REMARKS:

This report contains information that is intended solely for the use of the client and notice This report shall not be reproduced, except in full, without written approval of Te Lbr.163.Comp.186.Lab#21990